




We shall not be responsible or liable for any failure of, or damage to, this plumbing product caused by the use of chlorine/bleach cleaners or related products added to the tank water. Use of such products will void the warranty and may result in product failure, possibly causing property damage. Do not over tighten plastic nuts and always turn off water supply when installing / removing toilet cistern parts.

IMPORTANT: Some water companies may require a check valve to be installed before a fill valve. We take no responsibility for any failure to comply with installation requirements.



Please note: Save this instruction sheet for future reference IMPORTANT: DO NOT use plumber's putty to seal this fitting

For more information please contact:

VIVA Sanitary

Units 1-2 Capitol Trading Park, Kirkby Bank Road Knowsley Industrial Estate, Liverpool, L33 7SY

Tel: 0151 546 0531 Fax: 0151 549 4187 E-mail: sales@vivasanitary.co.uk

INSTALLATION INSTRUCTIONS



Determine whether thread size required is 1/2" (UK) or 3/8" (EURO).

If you require a bottom entry

distance from the bottom of

Secure the valve to the cistern

using the plastic washer and

nut. Do not over tighten.

installation, measure the

the cistern to the 6L level.

6L Level



for either side or bottom entry installations.

The height of the valve can be

easily adjusted once you twist

the base clockwise to unlock

and anticlockwise to re-lock.

The water level can be


adjusted by turning the

for less water).

adjustment screw (clockwise for more water, anticlockwise



To connect, screw the selected thread into the sprung loaded opening ensuring this is fully secure but not over tightened.




Place the valve in the correct position inside the cistern ensuring the conical rubber seal sits evenly inside the hole.




system, allowing the float to be rotated 180°. This is really beneficial if space is an issue.



The valve has a float rotation




The valve comes with a delayed fill function which delays the filling of the cistern until 5 seconds (approx.) after the start of a flush.




For the prevention of backflow from the cistern you must ensure the critical level of the fill valve is no less than 25mm higher than the cistern overflow level

TROUBLESHOOTING




Turn off the water supply and set access wheel to unlock.



Lift the top assembly away from the valve holding the arm.




Turn the water supply on and off to clear any debris. Hold a cup over the top to prevent any splashing.



Remove diaphragm washer and clean with water or replace.



Re-insert diaphragm washer.



Refit top assembly complete with diaphraam.



Join the Pro+ Installers club for exclusive benefits. www.vivasanitary.co.uk/pro



Scan QR code for installation video